BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Name of the Work :Improvements to Balance Roads and Drains AK Colony Singapura in Ward No. 11 (Kuvempunagara), Vidyaranyapura Sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	295.80	KSRRB M200-12.2 : Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T & P and scaffolding wherever necessary, sorting the dismantled materials, disposal of unserviceable material and stacking the serviceable material with all lifts and lead and lead of 10000 meters complete as per specifications. lime/cement concrete, I.by manual means B. cement concrete grade M-15 & M-20. **No. 136 / Item No. 18.18 / PWD SR 2015-16**	Cum	Rs.375.24	
2	418.18	KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3. **Page No. 141 / Item No. 19.1 / PWD SR 2015-16**	Cum	Rs.81.62	
3	438.75	Removing B.S Slab of Drain and stacking **Page No. 25 / Item No. 5.32 / PWD SR 2015-16**	Sqm	Rs.63.72	
4	438.75	Refixing stone slabs of drains and pointing in C.M (1:3) **Page No. 25 / Item No. 5.33 / PWD SR 2015-16**	Sqm	78.84	
5	68.40	KSRB 2.8 : Providing and filling in foundation with granite/trap broken metal 100mm, and down size, with approved sand including had packing, ramming, watering, including cost of all materials and labour with all lead and lift, complete as per specifications. Specification. No. KBS, **Page No. 6 / Item No. 2.15 / PWD SR 2015-16**	Cum	Rs.2,133.78	
6	181.20	KSRB 4-1.3 : Providing and laying in position plain cement concrete of **mix 1:4:8 with OPC cement @ 180 kgs with 40mm** and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2. **No. 12/ Item No. 4.3/ PWD SR 2015-16**	Cum	Rs.4,976.70	
7	1059.00	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for **vertical surface such as walls** at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 **Page No. 15 / Item No. 4.31 / PWD SR 2015-16**	Sqm	Rs.306.72	

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
8	247.90	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams. **Page No. 18 / Item No. 4.48 / PWD SR 2015-16**	Cum	Rs.6,332.04	
9	12.54	KSRB 4.9.2 : Providing **T .M.T steel reinforcement** for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 for TMT Bars Fe500 **(Page No 17., I.No.4.46.2 of KPWD S.R 2015-16).**	Tonne	Rs.59,327.91	
10	980.00	Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratiry, Power Floater, blade and disc etc., with all lead and lift No. **174 / Item No. 22.7 / PWD SR 2015-16**	Sqm	Rs.97.20	
11	100.00	Providing **groove cutting** for width of 5mm to 10mm and depth 80mm-100mm including cost of cutting machine, generator and HOM of machinery including cost of blade coolant etc including cleaning of groove and providing sand and hot bitumne fillars, and filler metal etc., indluding cost of converyance of all materials, labours, lead and lift charges and all other incidental charges as per drawing and as per specification **Concrete Pavement Page No. 175 / Item No. 22.8.1 / PWD SR 2015-16**	Sqm	Rs.124.20	
12	228.00	Providing **and Fixing precast RCC slab s of 100 mm thick** including cost of all materials,labour,curing,transportation,loading unloading,etc.,complete as per the direction of engineer in charge- Data rate	Sqm	Rs.1,760.00	
13	422.00	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C 1:2:4 with top and bottom width 114 and 165mm repectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including formwork curing, including, cost of all materials, labour hire charges of machinery, loading unloading, lead and lift, transportation etc, complete. **Page No. 25 / Item No. 5.30 / PWD SR 2015-16**	No.s	Rs.320.76	
14	66.50	KSRB 15.19.1 : Providing and applying ready mix **priming coat over concrete** / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after throughtly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications. **Page No. 121 / Item No. 15.80 / PWD SR 2015-16**	Sqm	Rs.27.00	

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
15	66.50	KSRB 15.20.1 : Providing and applying floor **painting with ready mix two coats** (Excluding priming coat) on new s concrete / masonry / asbestos cement sheet / / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications. **Page No. 121 / Item No. 15.83 / PWD SR 2015-16**	Sqm	Rs.51.84	
16	418.18	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km (Page No.123)	Cum	Rs.100.08	

~~Signature of the Contractor~~

Executive Engineer 29/9
Byatarayanapura Division
BBMP, Bangalore - 92

ಕರಡು ಟೆಂಡರ್ ಷಡ್ಯೂಲ್‌ನ್ನು
ಶಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ.....(Nil)
ಶಿದ್ದುಪಡಿ ~~ಮಾಡಿ~~/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿಲಾಗಿದೆ

29/9/16
Chief Engineer
Yelahanka Zone
Bruhath Bangalore Mahanagara
Rangalore 92

29.9.16